

**(TECHNICAL BID AND COMMERCIAL BIDS WILL BE SUBMITTED IN SEPARATE
SEALED ENVELOPES)**

Tele : 0532-2420772
Email: armyschoolalld@gmail.com

Army Public School
Rajiv Gandhi Marg
New Cantt, Allahabad-211 001


5077/Shed

20 Feb 22

INVITATION OF TENDER
ARMY PUBLIC SCHOOL, NEW CANT, ALLAHABAD
M.S. TRUSS AND ROOFING WORK AT ARMY PUBLIC SCHOOL, NEW
CANT, ALLAHABAD

1. You are invited by the Management of Army Public School, Allahabad to submit Tender for the above-mentioned work described in the accompanying documents
2. Your tender duly completed may be put in the tender box kept in school administration block on or before **12 Mar 2022** together with all relevant documents sealed in an envelope duly quoted your rates.
3. The following documents are included with this tender invitation:-
 - (a) Part I – General Specification about tender
 - (b) Part II – Technical Specification
 - (c) Part III – Price Bid
 - (d) Part IV – Terms & Condition
3. The Management of Army Public School, Allahabad doesn't bind itself to accept the lowest nor any tender and may cancel tendering process at any time.
4. Wherever there is difference between specification and drawings, specification will supersede the drawings.

(Signature with Stamp of Contractor)


Principal
Army Public School
New Cantt. Alla.



PART I - GENERAL INFORMATION ABOUT THE TENDER

Sr No.	Tender for the work of	M. S. TRUSS AND ROOFING WORK at Army Public School, New Cantt, Allahabad
1	Earnest money deposit	11,000/- Bank draft to be made in favour of Army Public School New Cantt, Allahabad (refundable)
2	Date of Issue of Tender	From 19 Feb 2022 to 12 Mar 22
3	Last Date of Receipt of Tender	12 Mar 22
4	This Tender Contains	11 Pages and Drawings
5	Time allotted for work	20 days from date of placing of work order
6	Site of the work	Army Public School, New Cantt, Allahabad.
7	Tender Cost	500/- Bank draft to be made in favour of Army Public School New Cantt, Allahabad. Not refundable.

(Signature with Stamp of Contractor)

Anshika
Principal
Army Public School
New Cantt. Allah

PART I - GENERAL INFORMATION ABOUT THE TENDER

1	NAME OF THE FIRM	
2	ADDRESS OF THE HEAD/ REGISTERED/ BRANCH OFFICE	
3	PHONE NO	
4	FAX NO	
5	MOBILE NO	
6	PAN NO	(Enclose proof)
7	GST NO	(Enclose copy of GSTN No. registration)
8	REGISTERED WITH GOVT.AGENCIES	(Enclose proof)
9	BANK ACCOUNT NO	
10	NAME & ADDRESS OF BANK	
11	CATEGORY OF TRADE	
12	NAME OF THE PARTNERS / PROPRIETOR	
13	EXPERIENCE IN YEARS IN THE RESPECTIVE TRADE	
14	SINGLE WORK ORDER DURING THE LAST TWO FINANCIAL YEARS	
15	PAYMENT DETAILS (Earnest Money)	Draft No: Date: Amount: Issuing Bank name and branch:

(Signature with Stamp of Contractor)

CERTIFICATE BY CONTRACTOR

In consideration of my being contractor, I hereby agree that I shall not withdraw, amend or attach any conditions to my tenders submitted to the school authorities. Said tenders of acceptance, and I do so, the Principal Army Public School, Allahabad shall be entitled to forfeit our earnest money deposit along with the tender and remove us from the school work contract without prejudice to any other right or remedy by school for such breach on our part.

(Signature with Stamp of Contractor)

[Faint signature and stamp of the contractor]

DECLARATION BY CONTRACTOR

I
(Proprietor/Partner/Manager) do here by declare that the entire declaration made in the application form is true to the best of my knowledge. [Note:- If there any changes in the construction of working of firm, the affecting accuracy of the answer now given, should be promptly communicated to The Principal, Army Public School, Allahabad.

(Signature with Stamp of Contractor)

PART II - TECHNICAL SPECIFICATION

Sr No.	Brief specification
1.	Fabrication, Supply & Fixing truss work of M.S. section as per specification in vertical post, purlins, rafters, gutter and truss completed with priming, painting and fixing all complete, with priming all exposed surface as per drawing, details & specification.
2.	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by school) 0.50 mm (+ 0.05 %) total coated thickness as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. Cost to include all providing and fixing accessories as approved make and model by school authority.
3.	Providing and painting of all exposed wall surface with textured exterior paint and all metal exposed surface with synthetic enamel paint both of approved colour, make, shade and texture with all tools and plants etc for proper completion of work as approved make and model by school authority.
5.	Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral coresandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc as approved make and model by school authority.
6.	All items will be as per IS specifications.


Principal
Army Public School
New Cantonment, Aligarh


PART III – PRICE BID (TO BE PROVIDED IN SEPARATE SEALED ENVELOPE)
EXPANSION OF STAGE AND M.S. TRUSS AND ROOFING WORK AT ARMY PUBLIC
SCHOOL, NEW CANTT, ALLAHABAD

Sr No.	Brief specification
1.	Fabrication, Supply & Fixing truss work of M.S. section as per specification in vertical post, purlins, rafters, gutter and truss completed with priming, painting and fixing all complete, with priming all exposed surface as per drawing, details & specification.
2.	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by school) 0.50 mm (+ 0.05 %) total coated thickness as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. Cost to include all providing and fixing accessories as approved make and model by school authority.
3.	Providing and painting of all exposed wall surface with textured exterior paint and all metal exposed surface with synthetic enamel paint both of approved colour, make, shade and texture with all tools and plants etc for proper completion of work as approved make and model by school authority.
5.	Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc as approved make and model by school authority.
6.	All items will be as per IS specifications.
7	Total Project cost Rs (Rupees _____) Including all taxes, transportations and all other levies

1. **Defect Liability Period.**

The defect liability period for the job is 01 years from date of completion of work. The Contractor shall be liable to repeat any defect noticed during defect liability period without payment of any extra cost to school. The Contractor shall be responsible to attend the defect within 15 days from notice given in writing, failing which the defects will be rectified through another agency at the risk and cost of the Contractor and amount recovered from the Performance Guarantee.

2. **5% of the total contract amount as Performance Guarantee will be kept**


Principal
Army Public School
New Cantt. Allahabad

reserve towards defects, if any observed, and will be released on successful completion of Defect Liability Period.

(Signature with Stamp of Contractor)

Nuhaka
Principal
Army Public School
1998-2001

PART IV – TERMS AND CONDITION
(GENERAL INFORMATION, INSTRUCTION AND CONDITION APPLIED)

1. Last date and time for issue/depositing this Tender is **12 Mar 2022**. Tender Bids received after this date and time even by post/ courier will not be entertained.
2. Sealed Bids by authorized contractor should be dropped in the Tender Box. No responsibility will be taken for postal delay or non-delivery/ non receipt of Bid documents. If the tenderer withdraws the tender before the said period or issue of letter of acceptance whichever is earlier or makes modifications in the terms & Condition of the tender which are not acceptable to the competent authority then the competent authority will be at liberty to forfeit 50% of the said earnest money.
3. **Location of the Tender Box**. Reception Office, Army Public School, New Cantt, Allahabad.
4. **Forwarding of Bids**. Bids should be forwarded by contractors on the prescribed format attached with the tender separately as technical and price bids. The technical bid should include the following details: -
 - (a) Technical Specifications.
 - (b) GSTN Number
 - (c) Bank Account No.
 - (d) Bank Address
 - (e) Complete Postal Address of Office.
 - (f) Office Landline and Mobile Phone Nos.
 - (g) E-mail Address of office (Optional).
 - (h) ITR of last two years.
5. **Rejection of Bids**. Canvassing by the Contractors in any form, unsolicited letter and posttender correction may invoke summary rejection with forfeiture of Earnest Money Deposit (EMD) conditional tenders will be rejected.
6. **Validity of Bids**. The Bids should remain valid for 90 days from the date of submission of bids.
7. **Earnest Money Deposit**. The tenderers' have to submit Bank draft for Rs 11,000/- (Rupees Eleven thousand only) in favour of " ARMY PUBLIC SCHOOL, NEW CANTT, ALLAHABAD" payable at Allahabad as EMD. The unsuccessful Contractors will be returned to them without any interest at the earliest on or before the 30th day after the award of the contract.
8. All the Taxes/ TDS will be deducted at the time of any payments as per defined/ eligible tax rate and authority will give proper documents of depositing the same amount to contractor/ suppliers.
9. The tenderers have to quote their rates both in figures and words. The rates quoted in the tender should be inclusive of all freight, taxes, service tax, GST and other incidental charges if any (i.e., F.O.R. School campus).
10. Every page of the tender should be signed (full signature) and rubber stamped by the tenderer. It should also be signed wherever there is overwriting and cutting.
11. All works services will be according to specification as per tender paper or subject to approval by the Board of Officers.
12. The successful contractor is solely responsible for the materials and labour

necessary for the completion of work.

13. The Contractor is responsible for periodic cleaning of the site during the construction process and removal of all construction material and debris at all time necessary, during and at the end of construction period.
14. The Contractor is responsible for ensuring all safety and security measure to be adhered to on site during the construction process including the safety of all students, staff and workmen along with the security of the site. Contractor will ensure that necessary screens are erected at work site to segregate the construction area from the school premises and ensure access to first floor is not available to students during the construction phase. Contractor will be held responsible for breach of security by him or his/ her workers about the school / cantarea, Allahabad military station. Covid protocol will be followed by the contractor.
15. The Contractor is required to ensure that measures are put in place to mitigate against all potential social and environmental impacts that can arise as a result of the use of equipment and machinery associated with the construction of the project.
16. The Contractor shall be deemed to have examined all documents, conditions of contract and to have acquainted himself with the detailed descriptions of the work to be done and the way in which they are to be carried out.
17. The Contractor shall be deemed to have visited the site before preparing his tender and to have examined for himself the conditions under which the works will process and all other matters affecting the carrying out the work and cost thereof.
18. The Contractor will maintain records of minimum wages to their labour any dispute in this regards will be dealt with directly by him and not by the school.
19. The construction work should be completed within **20 days** from the date of work order.
20. In case the work is not completed within the stipulated time frame, liquidated charges at the rate of 1% per week will be imposed on the Contractor subject to maximum of 10% of contract value. This amount will be adjusted from the bill of the Contractor.
21. The competent authority doesn't bind to accept the lowest or any other tender and reserves right to reject any or all the tenders received without the assignment of a person.
22. The Contractor shall submit minimum four progress report during the execution of work. This report shall be prepared in direct relation to the time stated in the contract documents for completion of items of work. A separate report will be given by the Contractor be made in writing by the Contractor.
23. All materials of construction work should be as per IS specifications as applicable.
24. **Arbitration Clause**. Decision of the Chairman, Army Public School, New Cantt, Allahabad will be binding to both parties. Place of arbitration for any legal dispute will be Allahabad.

25. Terms of Payments

(a) 95% of total contract amount will be paid after completion of all work of as perspecification after checking by a board of officers.

(b) Balance 5% of total contract amount shall be paid after completion of defectliability period of contract i.e. one year after successful completion of the work and rectification of defects, if noticed during the defect liability period.

(Signature with Stamp of Contractor)

N. N. N.
Principal
Army Public School
New Cantt. All

